PRIME

Prime Electrical Services, Inc
480 Enterprise Street
San Marcos, California 92078
Phone: (760) 471-6634
Fax: (760) 471-6636

August 14, 2008

Palomar College
1140 West Mission Road
San Marcos, CA 92069

SUBJECT: Terminate 12-Pair Voice Feed for Temporary Trailers

Here is our quote for the above-mentioned project. Our proposal is based on the following:

Material:	**$204.60**
Labor:	**$260.00**
Price Total	**$464.60**

Scope Of Work

- Splice the 12-pair in the SR-1 room to the 100-pair tail from the existing Lucent BEP (Building Entrance Protector) and on a new wall mounted 12-pair BEP at MB16.
- Run (3) 4-pair cables from the BEP to an existing rack mounted 24-port patch panel in MB16
- Test the 12-pair for opens and shorts.

All labor is at the prevailing wage labor rate on this project

Rich Landry

Project Manager

OK for Change Order 1
D Sullivan 8/14/08.